



RABINDRA BHARATI UNIVERSITY

Emerald Bower Campus: 56 A B.T. Road, Kolkata-700050

Jorasanko Campus: 6/4 Dwarakanath Tagore Lane, Kolkata-700007

Salt Lake Campus: Rabindra Bhavan, EE-9 & 10, Sector-II, Salt Lake City, Kol-91

PHONE: (033) E.B. Campus: 25571028, 3028, 4028, 7161 J.S. Campus: 22695241, 5242, 6601, 6610

Salt Lake Campus : 2358 4014-4016/4018 , Website : www.rbu.ac.in

RB / Engg/w/ 993 /2022

Date: 25.05.2022

TENDER NOTICE

Sealed tenders are invited for the rate of contract of different items of EPABX Cable and accessories as per the attached list within 7 days from the publication of the tender notice. The details of the tender will also be given on the University website. The decision of the University regarding selection will be final and binding for all tenderers.

Registrar

Quotation for rate contract of the following items of EPABX cables and accessories to be submitted as per the proforma given. Unit rate (basic price without tax) is to be given in the blank space and the tax will be paid extra. The rate should be valid for one year and the materials to be supplied as and when required.

Sl.No.	Item Description	Make	Qty.	Rate (Rs.)
01	Supplying and laying of 0.51mm dia 01 (Single) Pair Unarmored PVC cable.	Delton/Finolex	Per Mtr.	
02	Supplying and laying of 0.51mm dia 02 (Two) Pair Unarmored PVC cable.	Delton/Finolex	Per Mtr.	
03	Supplying and laying of 0.51mm dia 05 (Five) Pair Unarmored PVC cable.	Delton/Finolex	Per Mtr.	
04	Supplying and laying of 0.51mm dia 10 (Ten) Pair Unarmored PVC cable.	Delton/Finolex	Per Mtr.	
05	Supplying and laying of 0.51mm dia 20 (Twenty) Pair Unarmored PVC cable.	Delton/Finolex	Per Mtr.	
06	Supplying and laying of 0.51mm dia 50 (Fifty) Pair Unarmored PVC cable.	Delton/Finolex	Per Mtr.	
07	Supplying and laying of 0.51mm dia 10 (Ten) Pair Armored PVC cable.	Delton/Finolex	Per Mtr.	
08	Supplying and laying of 0.51mm dia 20 (Twenty) Pair Armored PVC cable.	Delton/Finolex	Per Mtr.	
09	Supplying and laying of 0.51mm dia 50 (Fifty) Pair Armored PVC cable.	Delton/Finolex	Per Mtr.	
10	Supplying and fixing of ten pair junction box (Fully GI sheet equipped with original ADC Krone model)		Each Set	
11	Supplying and fixing of twenty pair junction box (Fully GI sheet equipped with original ADC Krone model)		Each Set	
12	Supplying and fixing of fifty pair junction box (Fully GI sheet equipped with original ADC Krone model)		Each Set	
13	Supplying and fixing of hundred pair junction box (Fully GI sheet equipped with original ADC Krone model)		Each Set	
14	Supplying and laying $1\frac{1}{2}$ " casing with all accessories for cable laying		Per Mtr.	
15	Supplying and laying $\frac{3}{4}$ " casing with all accessories for cable laying.		Per Mtr.	
16	Supplying and laying 1" casing with all accessories for cable laying.		Per Mtr.	
17	Supplying and laying $\frac{3}{4}$ " PVC pipe.		Per Mtr.	
18	Supplying and laying 1 PVC pipe with all accessories for cable line.		Per Mtr.	
19	Supplying and fixing of RJ11 connector box with all accessories.		Per Mtr.	
20	6" x 6" Trench cutting charge for laying underground cable.		Per Mtr.	
21	Supplying and installation of 12 volt 24 AH maintenance free batter.	Exide	Each Set	
22	Supplying and installation of push button telephone set model BPL 5499.	BPL	Each Set	
23	Supplying and installation of push button telephone set model beetle M71	Beetle	Each Set	